BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Executive Engineeer Dasarahalli Division B.B.M.P, Bangalore - 73

SCHEDULE - B

Name of the Work :Providing Laying of tiles for pathway and laying kerb stones to pathway Indira canteen at pipeline road in Ward no 13 Shettyhalli Sub Div

Sl. No.	Description	Unit	Qty	Rates	
				In Figures	In Words
1	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications and directions of engineer in charge of the work	Cum	74.89	980.00	Nine Hundred Eighty Only
2	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of engineer in charge of the work	Sqm	149.78	210.00	Two Hundred Ten Only
3	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer and directions of engineer in charge of the work	Sqm	149.78	95.00	Ninty Five Only
4	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete and directions of engineer in charge of the work	Nos	139.00	330.00	Three Hundred Thirty Only
5	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications and directions of engineer in charge of the work	Sqm	144.90	28.00	Twenty Eight Only
6	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications and directions of engineer in charge of the work	Cum	144.90	70.00	Seventy Only

Scanned by CamScanner

	Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications and directions of engineer in charge of the work	Sqm	55.98	1250.00	One Thousand Two Hundred Fifty Only
8	Providing skirting, dadoing, rises of steps with white glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and directions of engineer in charge of the work	Sqm	9.00	1600.00	ONe Thousand Six Hundred Fifty Only
9	Providing and laying in position plain cement concrete of cum mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of engineer in charge of the work	Cum	16.42	5480.00	Five Thousand Four Hundred Eighty Only
10	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M20 for R.C.C works laid in 15 cms thick layers and well Oompacted by vibrating, curing, for raft foundation column footing, main and secondary beams with all lead and lifts etc., complete (exclusive Of cost of steel and fabrication charges) as per specifications and directions of engineer in charge of the work	Cum	16.28	6420.00	Six Thousand Four Hundred Twenty Only

Contractor Signature

Executive Engineer
Dasarahalli Division,
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57.

Scanned by CamScanner